

04 JAN 2024



CONTENT

INTRODUCTION.....	005
ADVANTAGES.....	019
PROCESS AND GUIDELINES.....	039
EXPRESSION.....	047
ON-SITE 3D PRINT.....	053
OFF-SITE 3D PRINT.....	075

INTRODUCTION

01

N3XTCON - NEXT GENERATION 3D-PRINTED CONCRETE STRUCTURES

N3XTCON is a project funded by Innovation Fund Denmark to develop a solution that brings 3D Concrete Printing to an industrial scale. As such, we move from the current experimental / exploration phase (i.e. small-scale demo projects without reinforcement) to a real productivity-increasing solution based on reinforced concrete.

The N3XTCON industrial solution paves the way for digital fabrication of the next generation of custom-made concrete structures that offers significant material savings and new architectural opportunities – all of it at lower costs when compared to traditional construction. Our development relies on current state-of-the-art knowledge on 3DCP and creates new knowledge on, 3DCP simulation based on material and print parameters, upscaling of materials from mortar to concrete and novel reinforcement strategies for 3DCP.



**WITH EVERY TECHNOLOGY COMES A REVOLUTION,
OFTEN WHERE APPLICATION LAGS BEHIND POTENTIAL**



**3D PRINTING IN CONSTRUCTION WAS FIRST EXPLORED IN THE 2000S,
AND IT IS NOW THAT WE'RE SEEING FEASIBLE APPLICATIONS**

7982 BC

1018




TIMBER
28 000 BC



STONE
10 000 BC



CLAY BRICK
7000 BC



CONCRETE
600 BC



GLASS
820 AD



TRUSS
27 900 BC



STONE LINTEL
Found towards the end of
the Neolithic Period
2500 BC



BRICK ARCH
Perfectured by the Romans
1400 BC



DOUBLE/TRIPLE GLAZING
First making an appearance
in Scotland
1800's



PRIMITIVE HUT
Origin of Architecture
27 900 BC

STONEHENGE
Amesbury, England
3100-1600 BC



GREAT PYRAMID
Cairo, Egypt
2560 BC



PARTHENON
Athens, Greece
432 BC



ROMAN AQUEDUCTS
Rome, Italy
312 BC



PANTHEON
Rome, Italy
126 AD



AMIENS CATHEDRAL
Amiens, France
1270

1918

2008

2017



STEEL
1851



ELEVATORS
First installed in the
Equitable Life Building
in New York
1870



REINFORCED CONCRETE
1877



PRECAST CONCRETE
Pioneered in Liverpool by
James Brodie
1905



CONCRETE FRAME STRUCTURE
Le Corbusier reinforced concrete to
create flexible interior space
1914-1915



MONOCOQUE STRUCTURE
First used for the Lotus 25
Formula 1 race car
1962



DIGITAL SOFTWARE
Autodesk releases their
first version
1982



POSSIBILITIES?
Present Day-Future



EIFFEL TOWER
Paris, France
1889



FLATIRON BUILDING
New York, North America
1902



PHILIPS PAVILION
Brussels, Belgium
1958



GATEWAY ARCH
St. Louis, North America
1963



SIDNEY OPERA HOUSE
Sidney, Australia
1973



BURJ KHALIFA
Dubai, United Arab Emirates
2010





**ITS ADVANTAGES LIE IN REDUCING HUMAN LABOR
WHILE INCREASING PRECISION AND SPECIFICITY**



**IN A MARKET DRIVEN BY ECONOMIES OF SCALE,
WHERE PROFIT IS ONLY FOUND IN BULK...**



**...WE ARE EXPLORING A NEW MODULARITY,
A BESPOKE KIT OF PARTS WITH THE FLEXIBILITY
TO ADAPT TO ANY CONDITION**

ADVANTAGES

02

Concrete, surpassing steel and wood in versatility, offers a globally available and cost-effective material. Its thermal mass behaviour curtails long-term energy costs and diminishes transportation expenses and associated CO2 emissions.

Combining concrete with 3D printing technology, exemplified by 3DCP, amplifies its inherent advantages. This construction approach enhances efficiency and minimizes physical labour, formwork, and waste, ultimately offering intensified design flexibility.


Concrete and 3D printing synergy showcases a sustainable and innovative solution with far-reaching implications for diverse applications. As a locally accessible resource worldwide, concrete, when harnessed through 3D printing, emerges as a powerful catalyst for efficient, eco-friendly construction practices, redefining the landscape of contemporary building methodologies.

CONCRETE AS A MATERIAL



Concrete stands out for its strength, durability, resilience, and safety. It adapts easily to various geometries through its fluidity and form works, fulfilling desired shapes. On average, the longevity of concrete buildings falls between 50 to 80 years.

Concrete production is more energy-efficient than steel, and although initial construction costs might exceed those of wood or steel, concrete structures offer long-term energy savings.



DURABILITY,
RESILIENCE, SAFETY



FORM VERSATILITY



50-80 YEAR
LIFESPAN



LONG-TERM ENERGY
SAVINGS COMPARED TO
WOOD/STEEL



LOWER ENERGY
COMPARED TO STEEL

CONCRETE PROPERTIES


When taking the performance of a building over its whole life cycle into account, concrete offers significant sustainability benefits over other building materials thanks to its innate properties, such as its durability, resilience, thermal mass, recyclability, carbon uptake and local availability. These attributes translate into tangible benefits: reduced energy consumption, significant carbon savings during transportation, minimized use of raw materials such as steel leading to decreased waste, and lowered construction costs; all collectively underscore concrete's environmentally conscious and economically viable character.



THERMAL MASSING




LOCAL AVAILABILITY



INNER ENVIRONMENT
NO USE OF PLASTIC




RECYCLING
AND RESUSING



STEEL REDUCTION





CONCRETE SUSTAINABILITY

KG CO₂ EQ / M3 OF CONCRETE



When comparing the global warming potential (GWP) of FutureCem to more typical types of concrete, we can see a noticeable reduction in GWP due to the difference in cement.

GLOBAL WARMING POTENTIAL



13 KG CO2 EQ /
M3 CONCRETE

7 KG CO2 EQ /
M3 CONCRETE

7 KG CO2 EQ /
M3 CONCRETE

3 KG CO2 EQ /
M3 CONCRETE


Although printing fast might use more energy, it does mean that the gantry printer would run for a shorter period of time. This leads to lower carbon emissions.

PRE-CAST VS PRINTED CONCRETE



PRECAST CONCRETE
GWP

291 KG CO₂ EQ /
M³ CONCRETE



GANTRY PRINTED CONCRETE
GWP

264 KG CO₂ EQ /
M³ CONCRETE*

* Numbers to be reduced further


Given the same amount of reinforcement, the Global Warming Potential of precast concrete is compared to that of 3D printed concrete using a gantry robotic printer. The concrete type used for our study is Generic, C20/25, precast concrete representative for Europe (1).

PRE-CAST VS PRINTED CONCRETE

CONVENTIONAL
CONSTRUCTION



3D
PRINTING



OPTIMIZED
EFFICIENCY




DECREASE IN
PHYSICAL LABOR



REDUCED WASTE
FROM FORMWORK




REDUCED
TRANSPORTATION



MORE DESIGN
FLEXIBILITY




OPTIMIZED EFFICIENCY




DECREASE IN PHYSICAL LABOR



REDUCED WASTE FROM FORMWORK



REDUCING TRANSPORTATION



DESIGN FLEXIBILITY


03


PROCESS AND GUIDELINES

To print concrete structures using a gantry crane robotic printer, we first derive the g-code from our 3D models. This is done through an intelligent connected system that automates the process. While this is happening, the concrete is prepared and the mixture is pumped from the concrete mixer to the print head. At the print head, a screw controls the amount of concrete extruded for a precise and uniform finish as the tool head moves along the three axes.



The gantry printing process results in a set of design guidelines and recommendations for an optimal print. While this process offers many new design opportunities, we must adapt our geometries to the principles and constraints that come with it.

GANTRY CRANE ROBOTIC PRINTER





PRINTING PROCESS



PRINTING PROCESS



Due to the nozzle geometry and printing motion, it is recommended to avoid sharp corners and use a minimum radius equal to the printhead diameter.



Due to the nozzle geometry and printing motion, it is recommended to avoid sharp corners and use a minimum radius equal to the printhead diameter.



For more efficient structures, 3D printing enables designers to replace solid infills with more optimized, lightweight ones.


DESIGN GUIDELINES



It is advised to locate the layer start and end points on the inner (hidden) sides of the walls since these locations are prone to over and under extrusion.



Achieving a closed top is only possible if we follow a curved section that would ideally be sloped less than 60° .



To structurally optimize geometries with slanted sections, curving them in plan could provide reinforcement.

DESIGN GUIDELINES






EXPRESSION

04




The expression of the prints can vary based on the material and the process of printing. Not only can we change the colors and intensities of the concrete, but 3D printing also offers the advantage of creating gradients in the concrete based on the order that the mixtures are poured in.

The surface texture and geometry could also be customized by editing some printing parameters. By varying parameters such as speed and toolpath, we can achieve variations of the regular layering that 3D printing offers.

COLOR + GRADIENT



TEXTURES + PATTERNS



05

ON-SITE PRINT

HENNING LARSEN


The proposal for an on-site 3D-printed concrete rowhouse, part of the N3XTCON innovation project, explores the fusion of aesthetics and sustainability.

The design uses simple curved wall elements to create a continuous, self-supporting structure, enhancing privacy between neighbours. The layout features an open-plan ground floor for kitchen and living functions, with bedrooms on the upper floor.

A 3D-printed curved staircase connects the floors, allowing circulation between 3D-printed services and spaces. Printing on-site allows the outer perimeter of slabs to be 3D-printed, minimizing concrete usage compared to traditional cast slabs.

This proposal exemplifies the aesthetic potential of on-site 3D-printed concrete and underscores sustainable construction practices.


The concept revolves around showcasing the aesthetics of 3D-printed concrete with sustainable design principles. A series of simple curved wall elements form the basis of the design, creating a continuous and self-supporting structure that simultaneously creates a private sphere between neighbours.



CONCEPT








The layout of the rowhouse consists of an open plan for kitchen and living room functions on the ground floor and bedrooms on the upper floor.

PLAN






A curved staircase between the wall and toilet core makes a sculptural connection between the floors and is imagined to be 3D printed.

LIVING






Both floors have a toilet/bath core that with 3D printed layout will offer a more considerable degree of freedom in using the print to form the interior of these zones.

BATHROOM






Both floors have a toilet/bath core that with 3D printed layout will offer a more considerable degree of freedom in using the print to form the interior of these zones.

BATHROOM




The façade contains two layers of 80mm concrete with stringers for support.

Between the ground floor and the first floor, a console is placed to carry the load of the wall above and transfer it to the inner wall below.








The slabs are suggested to be built on-site near the 3D-printed house. The construction consists of a 3D-printed outer perimeter cast with concrete after setting. Therefore, the 3D prints act as formwork to minimize the concrete used compared to a traditional cast slab.

SLAB PRINCIPLE






The slabs are suggested to be built on-site near the 3D-printed house. The construction consists of a 3D-printed outer perimeter cast with concrete after setting. Therefore, the 3D prints act as formwork to minimize the concrete used compared to a traditional cast slab.

SLAB PRINCIPLE







06

OFF-SITE PRINT


BJARKE INGELS GROUP



Prefabricated and modular 3D printed structures offer the combined advantages of both technologies. Due to many factors, off-site printing paves the way for faster progress during construction. While it offers some transportation constraints, we have developed a module that optimizes transportation space and weight. This innovative module not only streamlines logistics but also presents many geometric opportunities in the way it can be assembled.

The module is designed to stack shafts and structures while integrating the columns as formwork, reducing waste. The N3XTCON pineapple complex demonstrates the project and research on off-site printing and employs these advanced units as housing modules, envisioning a sustainable and interconnected community within a 3D-printed structure.

Simultaneously, completing modules and site work streamlines the construction process and minimises formwork, reducing waste production. The controlled factory environment enhances construction quality by averting weather-related delays. The swift assembly and disassembly also contribute to the ease and efficiency of construction. Moreover, off-site construction significantly curtails greenhouse gas emissions by approximately 30%. 3D printing for modules further accelerates construction, yielding substantial time and cost savings while offering more design flexibility. Incorporating eco-friendly insulation materials also has more potential for environmentally responsible design.


PREFABRICATED AND MODULAR 3D PRINTED STRUCTURES







Designing with off-site printing in mind comes with some restrictions that must be considered. The units must fit within the dimensions of the vehicles. It must also respect the weight limitations of the vehicle and the crane that will be installed onsite.

OFF-SITE CONSTRAINTS




The module outlined in the following pages is designed not only to respect transportation but also to optimize it. The module is designed in parts to fit two complete units and two halves per journey per truck.

MODULE PACKING



The maximum weight and print are first estimated as a straight wall. It is then curved to form an enclosed unit. The unit is then optimized, detailed and split into parts to facilitate printing and reduce transportation.

MODULE



The module is designed to stack shafts and structures. The stacking of the module also integrates the columns by acting as their formwork, further reducing waste by minimizing formwork.

CONTINUOUS STRUCTURE





RESIDENCES



OFFICES




The spaces generated by the module offer program flexibility and can be adapted to multiple uses. We have explored the potential of these units in the examples above, both as residential units and office spaces.

PROGRAM FLEXIBILITY



By stacking the modules in a checkerboard pattern, we can utilize the printed module and the spaces in between. We can print only half of the desired units, saving 50% of material and print time.

REDUCTION OF MATERIAL




DESIGN FLEXIBILITY




We have elaborated and explored the pineapple assembly further. The units are stacked and laid out in a radial format, and the modularity allows for various heights in the total massing. The pineapple can be prototyped at a smaller scale before its expansion into a more vertical structure.

PINEAPPLE



PINEAPPLE - SITE PLAN






PINEAPPLE - GROUND FLOOR PLAN






PINEAPPLE - TYPICAL FLOOR PLAN






PINEAPPLE - ROOF PLAN






PINEAPPLE - ZOOM IN PLAN







BALCONY SECTION




PROGRAM




RESIDENTIAL



SHARED SPACES



AMENITIES




PARKING/SERVICES


AREA m²							UNIT COUNT	EFFICIENCY
FLOOR	UNIT	OUTDOOR	CIRCULATION	COMMON	COMMERCIAL	GFA		
GF	82,94		52,79	15,28	153,09	304,1	3	17,36%
F01	233,48	24,78	70,71			328,97	9	23,25%
F02	233,48	24,78	70,71			328,97	9	23,25%
F03	233,48	24,78	70,71			328,97	9	23,25%
F04	233,48	24,78	70,71			328,97	9	23,25%
F05	233,48	24,78	70,71			328,97	9	23,25%
F06	233,48	24,78	70,71			328,97	9	23,25%
F07		167,74	24,62	136,6		328,96	0	15,27%
TOTAL	1483,82	316,42	501,67	151,88	153,09	2606,88	57	21,90%

BIKE PARKING	177,4 m²
DEPOT	211,5 m²
GARBAGE ROOM	70 m²
Total	458,9 m²

AREAS CALCULATION



CLOSED CORE FORMAT




EXPLODED AXO






THE MOCK UP



The module is 3D printed off-site, unit by unit, to maximize efficiency and meet transportation needs.







SUSTAINABILITY



EMBEDDED CO2

X



UNIT VOLUME




TOTAL VOLUME



DURABILITY


GLOBAL WARMING POTENTIAL (GWP)



6,5 kg CO2 eq / m2 / year*


* This study is only considering the embodied energy of the N3XTCON precast project in concept stage. The analysis uses a reference life span of 50 years and the floor area is 31,8 m2 taking part of the shared hall way and stair case into account.

UNIT GWP - MATERIALS WITH HIGHEST C FOOTPRINT



* This study is only considering the embodied energy of the N3XTCON precast project in concept stage. The analysis uses a reference life span of 50 years and the floor area is 31,8 m² taking part of the shared hall way and stair case into account.

UNIT GWP - MATERIALS WITH LOWEST C FOOTPRINT



GWP OF 1 FLOOR PLATE - MATERIALS WITH LOWEST C FOOTPRINT

3,4 kg CO₂ eq / m² / year
48510 kg CO₂ eq / floor plate / year*

far less than the Danish Building Regulations maximum of
12 kg CO₂ eq / m² / year

* This study is only considering the embodied energy of the N3XTCON precast project in concept stage. The analysis uses a reference life span of 50 years and the floor area is 287 m².

GWP OF 1 FLOOR PLATE - MATERIALS WITH LOWEST C FOOTPRINT

CONCRETE WALLS	REINFORCEMENT IN WALLS	INSULATION	WINDOW
Quantities for one unit 4,9 m3 concrete with FutureCem 2	Quantities for one unit 116 kg of steel	Quantities for one unit 8,9 m3 of insulation	Quantities for one unit 9 m2 of glass and 16,2 m mullions
Quantities for one floor plate 44 m3 concrete with FutureCem 2	Quantities for one floor plate 1043 kg of steel	Quantities for one floor plate 79 m3 of insulation	Quantities for one floor plate 81 m2 of glass and 146 m mullions
<p>Assumptions</p> <p>This study uses concrete with FutureCem 2 for the 3D printed walls. The ingredients ratio and specified aggregates are provided by the Danish Technological Institute (1).</p> <p>The footprint of one unit is 1,83 m2 and the height is 2,67 m. The concrete "pockets" around the reinforcement is assumed to be 200 mm x 300 mm.</p>	<p>Assumptions</p> <p>The amount of reinforcement is based on the assumption of 2 rebars of 12 mm diameter C-C 1000 mm. Additional 8 mm horizontal rebar every 300 mm. 23,7 kg reinforcement / m3 concrete.</p>	<p>Assumptions</p> <p>4 materials are being assessed for insulating the 3D printed walls: Concrete with FutureCem 1 (1), EPS (2), blown-in cellulose fibre insulation from recycled paper (3) and blown-in wood fibre insulation (4). Fire retardants: EPS: hydrogen bromide, Cellulose: boric acid and borax, Wood fibre: nitrogen and phosphorus and ammonium sulfate. Fire resistance class for EPS, Cellulose and Wood fibre: Euroclass E.</p>	<p>Assumptions</p> <p>The windows are triple glazing and two different materials are being compared for the mullions: pine and aluminium. The mullions are assumed to have a linear weight of 2,14 kg/m for the pine wood and 3 kg /m for the aluminium mullions. The glazing consists of 3 glass panes each 4 mm thick and with a 16 mm distance.</p>
Life cycle stages included A1-A3, A4, C3 and D	Life cycle stages included A1-A3, C4 and D	Life cycle stages included A1-A3, C4 and D	Life cycle stages included A1-A3, C3, C4 and D
Reference life span 60 years	Reference life span 80 years	Reference life span 80 (EPS), 60 (concrete), 50 (cellulose fibre), 60 (wood fibre)	Reference life span 20 (wood), 25 (glass)

MATERIAL SPECIFICATIONS FOR LCA

SLAB	TOP FLOOR	PRECAST STAIRS AND ELEVATOR SHAFT	RAILINGS FOR THE BALCONY
Quantities for one unit 31,8 m2 of concrete	Quantities for one unit 20 m2 of wood	Quantities for one unit 2,8 m3 of concrete, C45/55	Quantities for one unit 0,008 m3 of steel
Quantities for one floor plate 287 m2 of concrete	Quantities for one floor plate 180 m2 of wood	Quantities for one floor plate 25,4 m3 of concrete, C45/55	Quantities for one floor plate 0,07 m3 of steel
<p>Assumptions</p> <p>The slab is a precast concrete filigree slab and the reinforcement is assumed to be 150 kg steel / m3 of concrete (I). The slab is 80 mm thick.</p>	<p>Assumptions</p> <p>The entire floor inside each unit is assumed to be covered with 20 mm planks of oak.</p>	<p>Assumptions</p> <p>The central staircase and surrounding walls are included and the reinforcement is assumed to be 150 kg steel / m3 concrete for both stairs and elevator shaft.</p>	<p>Assumptions</p> <p>The railings are made of steel and weigh 62 kg pr balcony.</p>
Life cycle stages included A1-A3, C3 and D	Life cycle stages included A1-A3, C3 and D	Life cycle stages included A1-A3, C4 and D	Life cycle stages included A1-A3, C4 and D
Reference life span 75 years	Reference life span 60 years	Reference life span 60 years	Reference life span 80 years

MATERIAL SPECIFICATIONS FOR LCA





